



## **ADDENDUM – 1**

January 6, 2022

**PAWTUCKET HOUSING AUTHORITY  
Burns Manor  
Recirculation Water Line Replacement**

Project Site:  
**95 Park Street, Pawtucket, RI 02860**

The following changes, modifications, and clarifications are hereby made to the plans and specifications for the above referenced project.

Item 1: *Please clarify which water lines are being replaced.*

The project scope is to replace the existing copper re-circulation lines located within the corridor ceiling of buildings A, B, C & D with new PEX tubing. The contractor shall also furnish and install access panels as shown on contract plans to facilitate access to the existing re-circulation water line and unit shutoff valves.

See major scope items below:

Buildings A&D:

- Remove existing 3/4" copper re-circulation line and install new 3/4" PEX tubing and insulation.
- Furnish & install new 24x24 access panels.
- Replace existing unit shutoff valves with new ball-valves.
- Install new drain valve at each mechanical room.

Buildings B&C:

- Remove existing 1" copper re-circulation line and install new 1" PEX tubing and insulation.
- Furnish & install new 24x24 access panels.
- Replace existing unit shutoff valves with new ball-valves.
- Install new drain valve at each mechanical room.